

# Project Overview



## *East Brunswick, NJ Department of Public Works Office and Maintenance Facility*



The East Brunswick Director of Public Works wanted their existing building retrofitted with new exterior paneling. They chose to have Butler Shadowall™ installed over a new 3" layer of insulation.

There was minimal preparation required since the new panels were to be installed directly on top of the existing deteriorating wall panels. The existing secondary structural members were located to allow attachment with self-drilling screws. On a portion of the building, the panels were attached to masonry walls and self-tapping screws were used in those locations.



All of the new trims were custom field bent and cut out of flat-stock material with the exception of standard J-trim and base trim that was used over the doors, windows, louvers, and at the base of the walls.

The installation was a tremendous success and gave the building the look of being new.

Size: Existing Building Roof Area: 26,000 SF  
Wall Area: 19,000 SF

### Materials

Walls: Shadowall™ metal wall system

Trims: Standard and Custom Field Formed Trims

*"Tailored  
Construction Services"*

HANCE  
CONSTRUCTION, INC.

2171 Route 57  
Washington, NJ 07882

Phone: 908-835-3501

Fax: 908-835-3502

info@hanceconstruction.com

www.hanceconstruction.com

